

SURETY &  
REMONUMENTATION

1993

LIBER

1 PAGE 427

REMONUMENTATION  
COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

RECEIVED FOR RECORD

93 DEC 29 AM 10:54

LIBER NO. 1 PAGE NO. 427  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

<u>Sanilac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>14E</u>	<u>D - 1, C - 1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>Seg. 1</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, John A. Millettics, in a field survey on Dec 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

D - 1

Found Railroad Spike in paved surface, per survey dated 6-30-89

C - 1

Found P.K. nail in centerline of paved surface, per survey dated 8-8-81

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D - 1

N 1/4 Corner Section 5 T10N-R14E  
Found Railroad Spike

C - 1

NW Corner Section 5 T10N-R14E  
Found P.K. nail

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D - 1

N 1/4 Cor Section 5 T10N-R14E  
Set Monu Box  
South 51.35' to a ash stump  
N45°E 305.40' to a nail in a Power Pole  
N45°W 328.62' to a nail in a Power Pole  
East 2625.00' to the NE Cor Section 5

C - 1

NW Cor Section 5 T10N-R14E  
Set Monu Box  
N10°E 48.62' to the SE Cor of a Garage  
N10°W 48.70' to the SW Cor of a Garage  
N50°E 52.62' to a nail in a Power Pole  
S45°E 45.40' to a nail in a Power Pole

Signed by John A. Millettics

Date Dec 24, 1993

Surveyor's Michigan License No. 25859