

NOV 21 1997

COMMISSION

LIBER

2 PAGE 125

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 SEP -9 AM 8:57

LIBER NO. 2 PAGE NO. 125
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac
(County)

Located In:

Corner Code #

1. Public Land Survey

T 10NR 14E D - 1

T R

T R

T R

T R

2. Property Controlling
in Section

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

S

T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on June 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D - 1

GLO Notes not Available

APPROVED PEER BOARD MEETING

Aug 18, 1997 JAM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D - 1

N 1/4 Cor Section 5 T10N-R14E

Found Moun Box - removed by Sanilac County Road Comm. during reconstruction pf road. REPLACED using ACT 74 recorded in Liber 1 Page 427

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D - 1

N 1/4 Corner Section 5 T10N-R14E

Monu Box with iron and cap

South 51.35 to a nail in a ash stump

East 2625.00 to the NE Cor Section 5 (MONU BOX)

N45°E 305.40 to a nail in a Power Pole

N45°W 328.62 to a nail in a Power Pole

West 2622.96' to the NW Cor Section 5

Signed by

[Signature]

Surveyor's Michigan License No.

25859

Date

Aug 11, 1997

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

