

1993
REMONUMENTATION
COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac (County) Located In: Corner Code #

1. Public Land Survey T 10N R 14E G - 1, E - 1
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

RECEIVED FOR RECORD

93 DEC 29 AM 10:54

LIBER 1 PAGE NO. 428
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A. Milletics, in a field survey on Dec 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G - 1

Found 1/2" iron bar in paved surface, per survey dated 3-10-83

E - 1

Found P.K. nail in centerline of paved surface, per survey dated 8-8-1981

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G - 1

NE Corner Section 4 T10N-R14E
Found 1/2" iron bar

E - 1

NW Cor Section 4 T10N-R14E
Found P.K. nail

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G - 1

NE Corner Section 4 T10N-R14E
Set Monu Box
South 28.60' to the East end of a 12" CMP
S40°W 38.60' to the West end of a 12" CMP
North 1.10' to the centerline of Road
S05°E 91.90' to a nail in a 10" Ash

E - 1

NW Cor Section 4 T10N-R14E
Set Monu Box
North 20.45' to the East leg of a Road Sign
S30°E 38.50' to a stop sign
S45°W 85.90' to a nail in a Power Pole
North 2.40' to the centerline of the Road

Signed by John A. Milletics

Date Dec 24, 1993

Surveyor's Michigan License No. 25859