

REMONUMENTATION

NOV 21 1997

COMMISSION

LIBER 2 PAGE 127

REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

97 SEP -9 AM 8:57

LIBER NO. 2 PAGE NO. 127

ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T10N R14E	F - 1
	T R	
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4		3		2		1	
3													
4	7		8			9		10		11		12	
5													
6	18		17			16		15		14		13	
7													
8	19		20			21		22		23		24	
9													
10	30		29			28		27		26		25	
11													
12	31		32			33		34		35		36	
13													

I, John A. Milletics, in a field survey on June 21, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Note
No GLO Notes available

APPROVED PEER BOARD MEETING
Aug 18, 1997 JM

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F - 1
Found Monu Box - removed by Sanilac County Road Comm, during reconstruction of Road, Replaced using Act 74 recorded Liber 1 Page 443

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F - 1
N 1/4 Cor Section 4 T10N-R14E
MONU BOX
S30°W 69.25 feet to a nail in a 20" Maple
S60°E 101.05 feet to a nail in a 8" Ash
S05°E 61.00 to a nail in a 6" Ash
S50°W 101.63 feet to a nail in a 20" Maple
S70°E 92.52 to a nail in a Fence Post
S30°E 25.37 to a nail in a Mailbox
West 2622.24' to the NW Cor Section 4
East 2622.24' to the NE Cor Section 4

Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date Aug 15, 97

