

1993

REMONUMENTATION

COMMISSION

LIBER

1 PAGE 428

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac

(County)

Located In:

Corner Code #/

- 1. Public Land Survey T 10N R 14E
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

G - 1, E - 1

Seq-1

RECEIVED FOR RECORD

93 DEC 29 AM 10:54

LIBER 1 / PAGE NO. 428

ESTHER LEE

REGISTER OF DEEDS

SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A Milletics, in a field survey on Dec 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G - 1

Found 1/2" iron bar in paved surface, per survey dated 3-10-83

E - 1

Found P.K. nail in centerline of paved surface, per survey dated 8-8-1981

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G - 1

NE Corner Section 4 T10N-R14E  
Found 1/2" iron bar

E - 1

NW Cor Section 4 T10N-R14E  
Found P.K. nail

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G - 1

NE Corner Section 4 T10N-R14E  
Set Monu Box  
South 28.60' to the East end of a 12" CMP  
S40°W 38.60' to the West end of a 12" CMP  
North 1.10' to the centerline of Road  
S05°E 91.90' to a nail in a 10" Ash

E - 1

NW Cor Section 4 T10N-R14E  
Set Monu Box  
North 20.45' to the East leg of a Road Sign  
S30°E 38.50' to a stop sign  
S45°W 85.90' to a nail in a Power Pole  
North 2.40' to the centerline of the Road

Signed by

*John A. Milletics*

Date

Dec 24, 1993

Surveyor's Michigan License No.

25859