

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Locating Requirement of Act 74, Mich. P.A. 1970

For corners in
Sanilac

(County)

Located In:

Corner Code =#

- 1. Public Land Survey T10N R14E
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

G - 13

RECEIVED FOR RECORD

94 DEC 16 AM 9:39

LIBER NO. 1 PAGE NO. 481
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Milletics, in a field survey on Dec 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G - 13 GLO Notes
Set Post Corner: Beech 18 N75W 18, Beech 9 N75E 41
Act 74 Form NONE
Act 132 Form Liber 3 Page 313, Liber 3 Page 448
Unrecorded Surveys Dated 5-9-79,
Road Comm NONE
Drain Comm NONE


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G - 13
SW Cor Section 34 T10N-R14E
Found 1/2" Iron Bar

Approved Peer Board Meeting
Dec 16, 1994 jm

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G - 13
SW Cor Section 34 T10N-R14E
Found 1/2" Iron Bar
North 49.05 to a nail in a 12" Oak
N45°E 39.15 to a nail in a Brace Pole
S60°E 45.90 to a nail in a Wooden Fence Post
S45°E 53.80 to a nail in a Power Pole
East 65.60 to a 1/2" Iron Bar in the Road Bed



Signed by John A. Milletics
Surveyor's Michigan License No. 25859

Date Dec 11, 1994