

1993

LIBER 1 PAGE 418

RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

93 DEC 28 AM 10:39

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 1 PAGE NO. 418
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

<u>Sanilac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 10N R 14E	H - 1, I - 1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, John A Milletics, in a field survey on Oct 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H - 1
Found Railroad Spike in centerline of paved surface, per survey recorded in Liber 4, Page 255 of the Sanilac County Records.
- I - 1
Found Railroad Spike in the centerline of paved surface, per survey recorded in Liber 4, Page 255 of the Sanilac County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|-------------------------------|-----------------------------|
| H - 1 | I - 1 |
| N 1/4 Cor Section 3 T10N-R14E | NE Cor Section 3, T10N-R14E |
| Found Railroad Spike | Found Railroad Spike |

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|----------------------------------------|---------------------------------------------|
| H - 1 | I - 1 |
| N 1/4 Cor Section 3, T10N-R14E | NE Cor Section 3 T10N-R14E |
| Monu Box | Monu Box |
| N50°W 66.70' to a nail in a Power Pole | S35°W 78.35' to a nail in a Power Pole |
| N75°E 118.5' to a Road Sign | S35°E 73.50' to a nail in a 24" Ash |
| S75°E 122.4' to a tele box | N05°E 18.90' to the West leg of a Road Sign |
| East 2621.75 to the NE Cor Section 3 | West 2621.75' to the N 1/4 Cor Section 3 |

Signed by John A Milletics Date Dec. 24, 1993
 Surveyor's Michigan License No. 25859