

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE 94 DEC 16 AM 9:40

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac (County)

Located In:

Corner Code #

LIBER NO. 1 PAGE NO. 482
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

- 1. Public Land Survey T10N R 14E H - 13
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
- 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Milletics, in a field survey on Dec 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H - 13 GLO Notes
Set 1/2 Mile Post: Beech 16 N 2 W 18, Beech 7 N74E 28
Act 74 Form NONE
Act 132 Form NONE
Unrecorded Surveys Dated 5-9-79, Dated 12-12-90

Road Comm NONE
Drain Comm NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H - 13
S 1/4 Cor Section 34 T10N-R14E
Found 1/2" Iron Bar

Approved Peer Board Meeting
Dec 16, 1994 *jm*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H - 13
S 1/4 Cor Section 34 T10N-R14E
Found 1/2" Iron Bar
N45°W 80.45 to a spike in a 30" Beech
N70°E 102.85 to a spike in a 36" Maple
S45°E 65.20 to a PK Nail in a 8" Crabapple
South 43.40 to a PK Nail in a 6" Crabapple



Signed by *John A Milletics* Date Dec 11, 1994
Surveyor's Michigan License No. 25859