

1993

LIBER

1 PAGE 418

RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 28 AM 10:39

LIBER 1 PAGE NO. 418
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

<u>Sanilac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 10N R 14E	H - 1, I - 1
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John A. Millettics, in a field survey on Oct 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H - 1

Found Railroad Spike in centerline of paved surface, per survey recorded in Liber 4, Page 255 of the Sanilac County Records.

I - 1

Found Railroad Spike in the centerline of paved surface, per survey recorded in Liber 4, Page 255 of the Sanilac County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H - 1

N 1/4 Cor Section 3 T10N-R14E
Found Railroad Spike

I - 1

NE Cor Section 3, T10N-R14E
Found Railroad Spike

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

H - 1

N 1/4 Cor Section 3, T10N-R14E
Monu Box
N50°W 66.70' to a nail in a Power Pole
N75°E 118.5' to a Road Sign
S75°E 122.4' to a tele box
East 2621.75 to the NE Cor Section 3

I - 1

NE Cor Section 3 T10N-R14E
Monu Box
S35°W 78.35' to a nail in a Power Pole
S35°E 73.50' to a nail in a 24" Ash
N05°E 18.90' to the West leg of a Road Sign
West 2621.75' to the N 1/4 Cor Section 3

Signed by John A. Millettics Date Dec. 24, 1993

Surveyor's Michigan License No. 25859