

RECEIVED FOR RECORD

94 DEC 16 AM 9:40

LIBER NO. 1 PAGE NO. 483
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REMONUMENTATION
SURVEY &
REMONUMENTATION
APR 10 1995
COMMISSION

For corners in _____
San _____ Located In: _____ Corner Code # _____
(County)

- Public Land Survey T10N R 14E I - 13
T _____ R _____
T _____ R _____
T _____ R _____
- Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- Lot No. _____, Recorded Plat _____
- Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Milletics, in a field survey on Dec 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I - 13 GLO Notes
Set Post Corner: Sugar 11 N 54 W 24, Sugar 11 N 53 E 20
Act 74 Form NONE
Act 132 Form Liber 3 Page 255,
Unrecorded Surveys Dated 6-22-84, Dated 5-3-94

MDOT Right of Way Book Page 16 Show corner to south township being the same, Peer board rejected this.
Road Comm NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I - 13
SE Cor Section 34 T10N-R14E
Found 1/2" Iron bar

Approved Peer Board Meeting
Dec 16, 1994 SM

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I - 13
SE Cor Section 34 T10N-R14E
Found 1/2" Iron Bar
East 34.04 to a MONU BOX
N45°E 101.3 to a nail in a Road Sign Post
S20°E 91.47 to a spike in a Road Sign Post
S30°E 40.05 to a notch in the top of a 18" Conc Culvert
S70°W 139.4 to a nail in a 18" Pine



Signed by John A. Milletics

Date Dec. 11, 1994

Surveyor's Michigan License No. 25859