

1993

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Sanilac

COMMISSION

Located In:

Corner Code -#

LIBER NO. 1 DEED NO. 417
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

- 1. Public Land Survey T 10N R 14E J-1, K-1
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John A. Milletics, in a field survey on Oct 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J - 1

Found 1/2" iron bar in paved surface, per survey dated 5-10-85

K - 1

Found P.K. nail in centerline of paved surface.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J - 1

N 1/4 Cor Section 2 T10N-R14E

Found 1/2" iron bar

K - 1

NE Cor Section 2, T10N-R14E

Found P.K. nail

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J - 1

N 1/4 Cor Section 2 T10N-R14E

Monu Box

North 17.95' to the East leg of a Road Sign

N45°E 77.58' to a nail in a Power Pole

S45°E 77.90' to a nail in a Power Pole

S30°W 87.58' to a nail in a 24" Ash

K - 1

NE Cor Section 2 T10-R14E

Monu Box

North 17.15' to the West leg of a Road Sign

S45°W 42.45' to a nail in a Wooden Fence Post

S30°E 108.72' to a nail in a Power Pole

Signed by

John A. Milletics

Date Dec 24, 1993

Surveyor's Michigan License No.

25859