

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Sanilac Located In: _____ Corner Code # J-5
(County)

1. Public Land Survey	T <u>10N</u> R <u>14E</u>	I-5	<u>J-5</u>
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

RECEIVED FOR RECORD

95 SEP 27 AM 8:49

LIBER NO. 2 PAGE NO. 61
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on April 16, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I - 5	J - 5
GLO Notes	GLO Notes
Set Post B. Ash 15 S6½E 13	Set Post at 39.89
B. Ash 6 N6½W 13	Sugar 8 S4W 23
Act 74 None	Beech 6 N6W 27
Act 132 None	Act 74 None
Old Survey Liber Page 131 April 1902	Act 132 Nohe

Approved Peer Board Meeting
Sept 27, 1995 ML

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I - 5	J - 5
SE Cor Section 10 T10N-R14E	S 1/4 Corner Section 11 T10N-R14E
Found R/R Spike in Pavement	Found R/R spike in second layer of Blacktop

SURVEY &
REMONUMENTATION

OCT 26 1995

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-5	J - 5
SE Corner Section 10 T10N-R14E	S 1/4 Corner Section 11 T10N-R14E
Monu Box	Monu Box
N50°W 107.6 to a nail in a Power Pole	N45°E 68.3 to a nail in a Power Pole
N30°E 57.4 to a nail in a Power Pole	N45°W 68.0 to a nail in a Power Pole
S20°E 62.6 to a nail in a Power Pole	N30°W 61.4 to a Stop Sign
S25°E 62.3 to the NE Cor of a Shed	S30°E 44.0 to a Stop Sign

Signed by John A. Milletics Date: Sept 11, 1995
Surveyor's Michigan License No. 25859