

95 SEP 27 AM 8:48

LIBER NO. 2 PAGE NO. 60
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Sanilac
(County)

Located In: Corner Code #

- 1. Public Land Survey T 10N R 14E K-5 L-5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, John A Milletics, in a field survey on April 16, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
 - K - 5 L - 5
 - GLO Notes GLO Notes
 - Set Post Maple 20 N46W 19 Set Post at 39.66 Chains
 - Beech 9 S71½E 25 B. Ash 12 N8½E 20
 - Act 74 None Birch 6 S2W 9
 - Act 132 None Act 74 None
 - Road Comm None Old Survey Liber None
 - Drain Comm None Road Comm None
 - Drain Comm None Drain Comm None

Approved Peer Board Meeting
Sept 27, 1995 *[Signature]*

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 - K-5 L - 5
 - SE Corner Section 11 T10N-R14E S 1/4 Corner Section 12 T10N-R14E
 - Found R/R Spike 4" Deep in Pavement Found no sign of corner

SURVEY & REMONUMENTATION

OCT 26 1995

COMMISSION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K - 5 L - 5
- SE Corner Section 11 T10N-R14E S 1/4 Corner Section 12 T10N-R14E
- Moun Box Monu Box
- N45W 73.2 to a nail in a Power Pole N05°E 51.8 to a nail in a Power Pole
- N30W 52.5 to a Stop Sign N40°W 44.4 North end of a 18" CMP
- S40W 44.4 West end of a 24" CMP S40°W 36.3 South end of a 18" CMP
- S45E 45.0 East end of a 24" CMP North 5.8 to the centerline of pavement
- Set monu at half distance between corners half distance being 2617.00

Signed by *John A Milletics* Date Sept 11, 1995
Surveyor's Michigan License No. 25859