

1993

LIBER

1 PAGE 416

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in

Sanilac  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 10N R 14E L - 1, M - 1  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD

93 DEC 28 AM 10:39

LIBER NO. 1 PAGE NO. 416

ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO. MICHIGAN

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on Oct 7, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L - 1

Found P.K. nail in centerline of paved surface, per survey recorded in Liber 4, Page 245 of the Sanilac County Records.

M - 1

Found 5/8" iron bar in centerline of paved surface, per survey recorded in Liber 4, Page 245 of the Sanilac County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L - 1

N 1/4 Cor Section 1 T10N-R14E  
Found P.K. nail

M - 1

NE Cor Section 1 T10N-R14E  
Found 5/8" iron bar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L - 1

N 1/4 Cor Section 1 T10N-R14E  
Monu Box  
S30°E 52.15' to a nail in a Power Pole  
N55°W 68.70' to a nail in a 12" Ash  
S20°W 45.22' to a metal fence post

M - 1

NE Cor Section 1 T10N-R16E  
Monu Box  
N20°W 31.00' to a nail in a 24" Maple  
S45°W 69.35' to a nail in a Power Pole  
N20°E 29.90' to a nail in a 24" Maple  
N40°E 38.63' to a nail in a 24" Maple

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Signed by

*John A Milletics*

Date

Dec. 24, 1993

Surveyor's Michigan License No.

25859