

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 1 PAGE NO. 469  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

Sanilac

(County)

Located in:

Corner Code #

- 1. Public Land Survey T 10N R 14E M - 4, M - 5  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John A Milletics, in a field survey on July 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M - 4 Found no evidence of a existing corner on site

M - 5 Found 5/8" Iron bar in paved surface

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Approved Peer Board Meeting  
Aug. 9, 1994

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 4  
E 1/4 Cor Section 12 T10N-R14E  
Set 1/2" Iron straight line at half  
between NE cor and SE cor of Section

M - 5  
T10N-R14E  
Found 5/8" Iron Bar

SURVEY &  
REMONUMENTATION

SEP 07 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 4  
E 1/4 Cor Section 12 T10N-R14E  
1/2" iron bar in gravel road bed  
N80°E 34.50 to a nail in a 8" Pine  
N85°W 27.80 to the N End of a 24" CMP  
S60°W 31.40 to the S. End of a 24" CMP  
North 2615.00 to the NE Cor of Section 12  
South 2615.00 to the SE Cor of Section 12

M - 5  
SE Cor Section 12 T10N-R14E  
Monu Box  
N45°E 86.00 to a nail NW side of a Power Pole  
N45°W 60.40 to a nail SW side of a 8" Pine  
South 19.50 to the West leg of a Road Sign  
S70°E 60.10 to a Road Sign  
North 2615.00 to the E 1/4 Cor Section 12

Signed by [Signature]  
Surveyor's Michigan License No. 25859

Date July 23 1994