

LIBER

1 PAGE 413

RECEIVED FOR RECORD

93 DEC 28 AM 10:39

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE NO. 413
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 10N R 15E B - 1, C - 1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13 containing numbers 1-36.

I, John A Milletics, in a field survey on Oct. 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B - 1 Found no evidence of original corner in paved surface
C - 1 Found P.K. nail in centerline of paved surface.

SURVEY &
REMONUMENTATION
1993
COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B - 1 N 1/4 Cor Section 6 T10N-R15E Set monu box at a equal distance between the NE cor of Section 6 and the NW cor of Section 6
C - 1 NE Cor Section 6 T10N-R15E Found P.K. nail in centerline of paved surface.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B - 1 N 1/4 Cor Section 6 T10N-R16E Monu Box S05°W 34.30' to a metal fence post East 2592.12' to the NE Cor Section 6 West 2592.12' to the NW Cor Section 6
C - 1 NE Cor Section 6 T10N-R15E Monu Box N40°W 75.22' to a nail in a Power Pole S40°E 51.82' to a stop sign N60°W 36.35' to a mail box S45°W 37.55' to a nail in a Wooden Fence Post

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date Dec. 24, 1993