

93 DEC 15 PM 3:18

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 1 PAGE NO. 402
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac (County) Located In: Corner Code E-1

1. Public Land Survey T 10N R 15E E-1 D - 1
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on Nov 3, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E - 1 Found Monu Box, per survey recorded in Liber 4, Page 7 of the Sanilac County Records.

D - 1 Found 1/2" iron in blacktop, per survey dated Jan. 1987

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E - 1
NE Cor Section 5 T10N-R15E
Found Monu Box

D - 1
N 1/4 Cor Section 5 T10N-R15E
Found 1/2" iron in blacktop

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E - 1
NE Cor Section 5 T10N-R15E
Found Monu Box
North 17.70' to the East leg of a Road sign
S30°E 102.09' to a nail in a Power Pole
S40°W 121.07' to the NE Cor of a house
S50°W 116.85' to a nail in a 30"ash

D - 1
N 1/4 Cor Section 5 T10N-R15E
Found 1/2" iron
N05°E 29.35' to a nail in a 30" Maple
N70°W 61.00' to a nail in a 30" Maple
South 61.70' to a nail in a 20" Cherry

SURVEY &
REMONUMENTATION
1993
COMMISSION

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date Dec 15, 1993