

REMONUMENTATION

FEB 22 1996

LIBER 2 PAGE 77

RECEIVED FOR RECORD

95 DEC -6 PH 2:50

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 77
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

or corners in

Sanilac
(County)

Located In:

Corner Code: #

Public Land Survey

T 10N R 15E

F - 5 G - 5

T R
T R
T R

Property Controlling
in Section

S T R

Miscellaneous
Property in Sec.

S T R
S T R

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

John A. Millettics, in a field survey on Oct 6, 1995, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

F - 5

G - 5

GLO Notes

GLO Notes

Set 1/4 Post Hemlock 9 S27E 25
Hemlock 8 n15W 21

Set Cor Post Hemlock 22 N77E 20
Beech 4 S88W 11

Act 74 None

Act 74 None

Old Survey Liber Page 338 Dated March 1888

Old Survey Liber Page 338 Dated March 1888

Act 132 None

Act 132 Liber 423

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F - 5

G - 5

S 1/4 Cor. Section 9 T10N-R15E

SE Cor Section 9 T10N-R15E

Found P.K. Nail on straight line between

Found P.K. nail as recorded

SW and SE Cor at Half 2650.22'

Approved Peer Board Meeting

Dec 6, 1995 *JM*



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F - 5

G - 5

S 1/4 Cor Section 9 T10N-R15E

SE Cor Section 9 T10N-R15E

Monu Box

Monu Box

North 1.7' to road centerline

S45E 69.7 to a nail in a Power Pole

S45E 94.5 to a nail in a Power Pole

N20W 88.4 to the SW Cor of a House

East 2650.22 to the SE Section Cor

N20W 51.6 to a stop sign

West 2650.22 to the SW Section Cor

N60E 43.1 to a stop sign

igned by *John A. Millettics*

Date Nov 23, 1995

urveyor's Michigan License No. 25859