

REMONUMENTATION CORNER

LIBER

1 PAGE 400

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 15 PM 3: 18

LIBER NO. 1 ... DEED NO. 400  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

Sanilac  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 10N R 15E I - 1, H - 1
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A. Millettics, in a field survey on Nov 2, 19 92, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I - 1 Found 1" bar in gravel Road Bed, per survey recorded in Liber 1, Page 325 of the Sanilac County Records.

H - 1 Found no evidence of original corner in existence.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I - 1	H - 1
NE Cor Section 3 T10N-R15E	N 1/4 Cor Section 3 T10N-R15E
Found 1" Bar in Road Bed	Set 1/2" iron with cap(25859) at a equal distance between the NE Cor and the NW Cor of the Section.(2624.04'

SURVEY & REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I - 1	H - 1
NE Cor Section 3, T10N-R15E	N 1/4 Cor Section 3, T10N-R15E
Found 1" bar	Set 1/2" iron bar with cap(25859)
South 33.00' to a 1/2" iron bar	S45°W 46.30' to a nail in a 12" Poplar
S40°E 43.90' to a nail in a Fence Post	S45°E 49.00' to a nail in a 10" Poplar
S50°E 52.85' to a nail in a Fence Post	N80°E 140.95' to the north end of a 36" CMP
S60°E 62.60' to a nail in a Fence Post	

Signed by John A. Millettics Date Dec 17, 1993

Surveyor's Michigan License No. 25859