

REMONUMENTATION

FEB 22 1996

LIBER 2 PAGE 76

RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

95 DEC -6 PM 2: 50

LIBER NO. 2 PAGE NO. 76
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN.

For _____

 (County)

Located In: _____ Corner Code # _____

1. Public Land Survey T 10N R 15E H - 5 I - 5
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

John A Milletics, in a field survey on Oct 6, 19 95,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 H - 5 I - 5
 GLO Notes GLO Notes
 Set 1/4 Post at 39.90 Spruce 3 North 7 Set Cor Post Cedar 9 N57E 16
 Spruce 4 S10E 20 Cedar 7 S45W 17
 Act 74 None Act 74 None
 Act 132 None Act 132 None
 Old Survey Liber None Old Survey Liber Page 336 April 1890. Page 344
 Oct 1890. Page 402 Nov 1893

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 H - 5 I - 5
 S 1/4 Cor Section 10 T10N-R15E SE Cor Section 10 T10N-R15E
 Found 1/2" Iron bar on line between Found P.K. Nail in bridge deck
 SE and SW Cors at Half 2632.64'

Approved Peer Board Meeting
 Dec. 6, 1995 JM



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 H - 5 I - 5
 S 1/4 Cor Section 10 T10N-R15E SE Cor Section 10 T10N-R15 E
 1/2" iron bar in gravel road bed P.K. Nail in Bridge Deck
 N30W 23.6 to the North end of a 24" CMP East 5.0 to a 1/2" Iron Bar
 S30W 18.8 to the South end of a 24" CMP North 50.00 to a 1/2" Iron Bar
 East 2632.64 to the SE Cor North 7.3 to the N. Edge of the Bridge Deck
 West 2632.64 to the SW Cor N70°W 27.5 to the North cor of NW Wing Wall
 S70°W 27.9 to the South cor of SW Wing Wall

Signed by John A Milletics Date Nov 23 1995
 Surveyor's Michigan License No. 25859