

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

1 PAGE 396

For corners in

Sanilac (County) Located In: Corner Code #

1. Public Land Survey T 10N R 15E K - 1, J - 1
 T ___ R ___
 T ___ R ___
 T ___ R ___

2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECEIVED FOR RECORD
 93 DEC 15 AM 9:15
 LIBER 1 PAGE NO. 396
 REGISTER OF DEEDS STAMP & FILE NUMBER
 SANILAC CO., MICHIGAN

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A. Millerics, in a field survey on Nov 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- K - 1 Found 1" bar in gravel road bed, per survey recorded Liber 1, Page 325 of the Sanilac County Records.
 - J - 1 Found 1/2" iron in gravel road bed, per survey recorded Liber 1, Page 325 of the Sanilac County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K - 1	J - 1
NE Cor Section 2 T10N-R15E	N 1/4 Cor Section 2 T10N-R15E
Found 1" iron bar	Found 1/2" iron bar

SURVEY &
 REMONUMENTATION
 1993
 COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K - 1	J - 1
NE Cor Section 2 T10N-R15E	N 1/4 Cor Section 2 T10N-R15E
Found 1" bar	Found 1/2" iron bar (capped 25859)
N45°E 44.10' to a nail in a Anchor Pole	S80°E 174.60' to a nail in a Power Pole
S45°E 45.30' to a nail in a Power Pole	South 33.00' to a 1/2" iron
S30°W 77.60' to a nail in a Tele Pole	East 2626.0' to the NE Cor Section 2
North 14.50' to the East leg of a Road Sign	

Signed by John A. Millerics Date Dec 14, 1993
 Surveyor's Michigan License No. 25859