

SURVEY & REMONUMENTATION

RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

94 DEC 16 AM 9:41

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 13

For corners in

Sanilac (County)

APR 10 1995

COMMISSION

Located In:

Corner Code ##

ESTHER LEE REGISTER OF DEEDS SANILAC CO., MICHIGAN

- 1. Public Land Survey T 10N R 15E J - 11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 2-13 containing numbers 1-36.

I, John A. Milletics, in a field survey on Aug 29, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: J - 11 GLO Notes Set 1/4 Section Post: Tamk 12 S 19 E 17, Tamk 12 N 9 W 23 Act 74 Form Liber 1 Page 5 Act 132 Form Liler 3 Page 49, Unrecorded survey Dated 3-29-88 MDOT Right of Way Book Page 56 Road Comm NONE Drain Comm NONE

Approved Peer Board Meeting Dec. 16, 1994 gm

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: J - 11 S 1/4 Cor Section 26 T10N-R15E Found Moun Box - Raised Monu Box during Resurfacing

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: J - 11 S 1/4 Cor Section 26 T10N-R15E Found Monu Box South 33.00 to a 1/2" Iron(6504) South 31.90 to a nail in a 18" Maple N50°E 48.75 to a nail in a Wooden Fence Post N45°W 43.50 to a stop sign Monu Box exist on Road Centerline



Signed by [Signature] Date Dec. 11, 1994

Surveyor's Michigan License No. 25859