

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER

1 PAGE 396

For corners in

Sanilac Located In: Corner Code ~~##~~

(County)

1. Public Land Survey T 10N R 15E K-1, J-1
T ___ R ___
T ___ R ___
T ___ R ___

2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___

3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECEIVED FOR RECORD

93 DEC 15 AM 9:15

LIBER NO. 1 / PAGE NO. 396
REGISTER OF DEEDS STAMP & FILE NUMBER
SANILAC CO., MICHIGAN

I, John A Millettics, in a field survey on Nov 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

K - 1 Found 1" bar in gravel road bed, per survey recorded Liber 1, Page 325 of the Sanilac County Records.

J - 1 Found 1/2" iron in gravel road bed, per survey recorded Liber 1, Page 325 of the Sanilac County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K - 1
NE Cor Section 2 T10N-R15E
Found 1" iron bar

J - 1
N 1/4 Cor Section 2 T10N-R15E
Found 1/2" iron bar

SURVEY & REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K - 1
NE Cor Section 2 T10N-R15E
Found 1" bar
N45°E 44.10' to a nail in a Anchor Pole
S45°E 45.30' to a nail in a Power Pole
S30°W 77.60' to a nail in a Tele Pole
North 14.50' to the East leg of a Road Sign

J - 1
N 1/4 Cor Section 2 T10N-R15E
Found 1/2" iron bar(capped 25859)
S80°E 174.60' to a nail in a Power Pole
South 33.00' to a 1/2" iron
East 2626.0' to the NE Cor Section 2

Signed by John A Millettics Date Dec 14, 1993
Surveyor's Michigan License No. 25859