

94 DEC 16 AM 9:41

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

SURVEY & Filing Requirement of Act 74, Mich. P.A. 1970

For corners in REMONUMENTATION

LIBER NO. 2 PAGE NO. 15
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Sanilac
(County)

Located In:

Corner Code #

APR 10 1995

- 1. Public Land Survey T 10N R 15E L - 11
COMMISSION R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Milletics, in a field survey on Sept 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L - 11 GLO Notes
Set 1/4 Section Post: Tamk 12 N 56 E 1.19, Willow 4 S 55 1/2 W 42

Act 74 Form NONE
Act 132 Form NONE

Unrecorded Surveys Dated 7-16-66, Dated 5-14-80, Dated 6-16-87, Dated 3-31-88

MDOT Right of Way Book Page 57

Approved Peer Board Meeting
Dec. 16, 1994 *gm*

Road Comm NONE
Drain Comm NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L - 11
S 1/4 Corner Section 25 T10N-R15E
Found Monu Box - Raised Monu Box during Resurfacing

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L - 11
S 1/4 Cor Section 25 T10N-R15E
Found Monu Box
N70°W 27.00 to a Bridge Pillor
S70°W 27.30 to a Bridge Pillor
N45°E 26.40 to the back edge of the thrid guard rail post
N10°W 28.85 to the back edge of the end guard rail post



Signed by *John A Milletics* Date Dec 11, 1994
Surveyor's Michigan License No. 25859