

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER

1 PAGE 397

For corners in

Sanilac
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 10N R 15E M-1, L-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

RECEIVED FOR RECORD

93 DEC 15 AM 9:15

LIBER NO. PAGE NO. 397
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13 containing numbers 1-36.

I, John A Milletics, in a field survey on Nov 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M - 1 Found 1/2" iron NE of gravel turn, as per survey dated 11-08-1990 Milletics Land Surveying.
L - 1 Found Railroad Spike in gravel road bed, as per survey dated 7-1-1986 Milletics Land Surveying.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M - 1 NE Cor Section 1 T10N-R15E Found 1/2" iron
L - 1 N 1/4 Cor Section 1 T10N-R15E Found Railroad Spike

SURVEY &
REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M - 1 NE Cor Section 1 T10N-R15E Found 1/2" iron (cap 25859)
N05°W 19.75' to a nail in a 10" Poplar
S45°E 62.60' to a nail in a Power Pole
S02°E 16.80' to the east leg of a Road Sign
West 28.70' to the south leg of a Road Sign
L - 1 N 1/4 Cor Section 1 T10N-R15E Set 1/2" iron with cap(25859)
S05°W 31.20' to a nail in a Power Pole
N40°W 38.10' to a nail in a Maple Stump
N60°W 47.60' to a nail in a 20" Maple
N80°W 81.05' to a nail in a 36" Maple

Signed by John A Milletics Date Dec. 14, 1993

Surveyor's Michigan License No. 25859