

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 AUG 12 PM 2:37

LIBER NO. 1 PAGE NO. 463
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac
(County)

Located In:

Corner Code #

- 1. Public Land Survey T10N R15E M-2, M-3
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

John A Milletics in a field survey on July 12, 19 94
Do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- M - 2 Found R/R Spike in gravel road bed as recorded in Liber 4 on Page 84 of the Sanilac County Records
- M- 3 Found 1/2" iron in gravel road bed as recorded in Liber 4 on Page 84 of the Sanilac County Records.

Approved Peer Board Meeting
Aug. 9, 1994

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M - 2
E 1/4 Cor Section 1 T10N-R15E
Found R/R Spike
- M - 3
SE Cor Section 1 T10N-R15E
Found 1/2" Iron

SURVEY &
REMONUMENTATION

SEP 07 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M - 2
E 1/4 Cor Section 1 T10N-R15E
R/R Spike
East 33.00 to a 1/2" iron bar
N45°W 43.75 to a nail SW Side of a Fence Post
S80°W 31.40 to a stop sign
S50°W 29.60 to the S End of a 12" CMP
North 4262.50 to the NE Cor of Section 1
- M - 3
SE Cor Section 1 T10N-R15E
1/2" Iron Bar
S45°W 80.00 to a nail NW side of a Power Pole
N45°W 45.25 to a nail NE side of a 36" Willow
N45°E 41.75 to a nail NW side of a Fence Post
S45°E 53.20 to a nail NW side of a 12" Cedar

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date July 23, 1994