

LAND CORNER RECORDATION CERTIFICATE

94 AUG 12 PM 2: 38

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 1 PAGE NO. 464

For corners in

Sanilac

(County)

Located In:

Corner Code -#

1. Public Land Survey

T 10N R 15E

M - 4, M - 5

2. Property Controlling in Section

S T R

3. Miscellaneous

S T R

Property in Sec.

S T R

4. Lot No. , Recorded Plat

5. Private Claims

ESTHER LEE REGISTER OF DEEDS SANILAC CO. MICHIGAN

Register of Deeds Stamp & File Number

John A Milletics in a field survey on July 12 19 94

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M - 4 Found 1/2" iron bar in gravel road bed per Irvin E. Chope survey dated 7-28-1976

M - 5 Found 3" angle iron in gravel road bed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 4 E 1/4 Cor Section 12 T10N-R15E Found 1/2" Iron Bar

M - 5 SE Cor Section 12 T10N-R15E Found 3" Angle Iron

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 4 E 1/4 Cor Section 12 T10N-R15E 1/2" Iron Bar East 33.00 to a 1/2" Iron Bar West 33.00 to a 1/2" Iron Bar S80°W 51.4 to a nail N side of a Tele Pole S30°E 26.0 to a nail W side of a 10" Ash North 2632.20 to the NE Cor of Section 1.

M - 5 SE Cor Section 12 T10N-R15E 3" Angle Iron N40°E 64.20 to a nail SE side of Fence Post N70°E 48.50 to a stop sign S70°W 35.00 to a stop sign East 2501.05 to the S 1/4 Cor Section 1

Approved Peer Board Meeting Aug. 9, 1994

Signature

gm

Grid table with columns A-M and rows 1-13. Numbers 1-36 are placed in the grid cells.

SURVEY & REMONUMENTATION

SEP 07 1994

COMMISSION

Signed by John A Milletics

Date July 23, 1994

Surveyor's Michigan License No. 25859