

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 AUG 12 PM 2: 38

LIBER NO. 1 PAGE NO. 464
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac
(County)

Located In:

Corner Code #

1. Public Land Survey	T	10N	R	15E	M - 4, M - 5
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

John A Milletics, in a field survey on July 12, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M - 4 Found 1/2" iron bar in gravel road bed per Irvin E. Chope survey dated 7-28-1976

M - 5 Found 3" angle iron in gravel road bed

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 4
E 1/4 Cor Section 12 T10N-R15E
Found 1/2" Iron Bar

M - 5
SE Cor Section 12 T10N-R15E
Found 3" Angle Iron

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 4
E 1/4 Cor Section 12 T10N-R15E
1/2" Iron Bar
East 33.00 to a 1/2" Iron Bar
West 33.00 to a 1/2" Iron Bar
S80°W 51.4 to a nail N side of a Tele Pole
S30°E 26.0 to a nail W side of a 10" Ash
North 2632.20 to the NE Cor of Section 1.

M - 5
SE Cor Section 12 T10N-R15E
3" Angle Iron
N40°E 64.20 to a nail SE side of Fence Post
N70°E 48.50 to a stop sign
S70°W 35.00 to a stop sign
East 2501.05 to the S 1/4 Cor Section 1

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Approved Peer Board Meeting
Aug. 9, 1994

[Signature]
gm

SURVEY &
REMONUMENTATION

SEP 07 1994

COMMISSION

Signed by John A Milletics
Surveyor's Michigan License No. 25859

Date July 23, 1994