

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 AUG 12 PM 2:38

For corners in

LIBER NO. 1 PAGE NO. 466

Sanilac (County) Located In: Corner Code #

1. Public Land Survey T 10N R 15E M - 8, M - 9
 T R
 T R
 T R

2. Property Controlling S T R
 in Section S T R
 3. Miscellaneous S T R
 Property in Sec. S T R

4. Lot No. , Recorded Plat
 5. Private Claims

ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on July 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M - 8 Found P.K. nail in centerline of Blacktop as per survey dated 10-01-80 Sanilac Land Surveying.

M - 9 Found R/R Spike in centerline of Blacktops as per survey dated 10-01-80 Sanilac Land Surveying.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Approved Peer Board Meeting
Aug. 9, 1994

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 8
E 1/4 Cor Section 24 T10N-R15E
Found P.K. Nail

M - 9
SE Cor Section 24 T10N-R15E
Found R/R Spike

SURVEY &
REMONUMENTATION

SEP 07 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 8
E 1/4 Cor Section 24 T10N-R15E
Moun Box
West 50.00 to a 1/2" Iron Bar
West 50.50 to a nail S side of a Power Pole
East 50.00 to a 1/2" Iron Bar
S80°E 42.1 to the N end of a 12" CMP
North 2620.00 to the NE Cor of Section 24

M - 9
SE Cor Section 24 T10N-R15E
Monu Box
S20°W 35.80 to a nail SE side of a 24" Maple
N45°W 73.40 to a nail SW side of a Power Pole
S70°W 77.00 to a nail N side of a 24" Maple
North 2631.14 to the E 1/4 Cor Section 24

Signed by [Signature] Date July 23, 1994

Surveyor's Michigan License No. 25859