

94 AUG 12 PM 2:38

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 1 PAGE NO. 467  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

Sanilac Located In: Corner Code #  
(County)

1. Public Land Survey T 10N R 15E M - 11  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on July 13, 19 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
M - 11 Found Monu Box centerline of M-90 and Cribbins Road  
in pavement as per State Highway R/W Book and survey dated 5-19-1982  
Sanilac Land Surveying.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Approved Peer Board Meeting  
Aug. 9, 1994

*[Signature]*  
*gm*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
M - 11  
SE Cor Section 25 T10N-R15E  
Found Monu Box

SURVEY & REMONUMENTATION

SEP 07 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
M - 11  
SE Cor Section 25 T10N-R15E  
Monu Box  
N20°E 72.50 to a nail W side of a 20" Pine  
S45°W 54.30 to a nail NW side of a Tele Pole  
S60°W 81.90 to a concrete R/W Marker  
S30°E 54.00 to a stop sign

Signed by *John A Milletics* Date July 23, 1994  
Surveyor's Michigan License No. 25859