

94 AUG 12 PM 2: 38

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 1 PAGE NO. 468  
ESTHER LEE  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

Sanilac (County) Located in: Corner Code #/

1. Public Land Survey T 10N R 15E M - 12, M - 13  
 T R  
 T R  
 T R

2. Property Controlling S T R  
 in Section S T R  
 3. Miscellaneous S T R  
 Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

John A Milletics, in a field survey on July 13, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 M - 12 Found 1/2" Iron Bar in Gravel Road Bed, per survey dated 5-14-1980 Sanilac Land Surveying

M - 13 Found 1/2" iron bar in gravel road bed, per Choape survey recorded in Liber 3 on Page 5 of the Sanilac County Records.

Approved Peer Board Meeting  
 Aug. 9, 1994 *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 12  
 E 1/4 Cor Section 36 T10N-R15E  
 Found 1/2" Iron Bar

M - 13  
 SE Cor Section 36 T10N-R15E  
 Found 1/2" Iron Bar

SURVEY & REMONUMENTATION

SEP 07 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 12  
 E 1/4 Cor Section 36 T10N-R15E  
 1/2" Iron Bar  
 N85°W 47.30 to a nail S side of a Fence Post  
 West 50.00 to a 1/2" Iron Bar  
 S30°W 64.50 to the N End of a 36" CMP  
 S25°W 93.30 to the S End of a 36" CMP

M - 13  
 SE Cor Section 36 T10N-R15E  
 1/2" Iron Bar  
 N40°E 55.40 to a nail NW side of a Power Pole  
 S50°W 50.30 to a stop sign  
 N70°E 47.90 to a stop sign  
 S30°W 62.50 NE cor of a Michigan Bell Box

Signed by *[Signature]*  
 Surveyor's Michigan License No. 25859

Date July 23, 1994