

FEB 22 1996

LIBER 2 PAGE 73

RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

95 DEC -6 PH 2:49

LIBER NO. 2 PAGE NO. 73
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

For corners in

Sanilac
(County)

Located in:

Corner Code ##

- 1. Public Land Survey T10N R 16E B - 5 D - 5
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

John A Milletics in a field survey on Oct 13, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B - 5
GLO Notes
Set Post at 37.80 - 40.00
Maple 7 North 14
Cedar 9 S36W 19
Act 74 Liber 1 Page 271
Act 132 Liber 2 Page 340
Old Survey Liber Page 301
- D - 5
GLO Notes
Set 1/4 Post at 40.34
B Ash 14 S26W 4
B Ash 17 N02W 48
Act 74 None
Act 132 None
Old Survey Liber None

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B - 5
S 1/4 Cor Section 7 T10N-R16E
Found 5/8" Iron Bar
- D - 5
S 1/4 Cor Section 8 T10N-R16E
Found R/R Spike in Blacktop

Approved Peer Board Meeting

Dec 6, 1995 *JM*



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B - 5
S 1/4 Cor Section 7 T10N-R16E
5/8" Iron Bar in gravel road bed
North 33.00 to a 1/2" Iron Bar
N45W 40.35 to a nail in a Multi Apple
S05W 25.27 to a nail in a Fence Post
S40E 30.6 to a nail in a 12" Ash
- D - 5
S 1/4 Cor Section 8 T10N-R16E
Monu Box
South 2.1' to the centerline of Road
West 9.0' to the centerline of R/R Tracks
N50°W 76.0' to a nail in a Power Pole
N45°E 70.95 to a nail in a Power Pole

Signed by *John A. Milletics*

Date Nov 23, 1995

Surveyor's Michigan License No. 25859