

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 1 PAGE NO. 403
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac
(County)

Located In:

Corner Code ~~##~~

- 1. Public Land Survey T 10N R 16E C-1, D-1
T R
T R
T R
- 2. Property Controlling S T R
in Section S T R
- 3. Miscellaneous S T R
Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	N
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A. Milletics, in a field survey on Nov 5, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C - 1 Found 1/2" iron in gravel road bed, per survey recorded in Liber 4, Page 58 of the Sanilac County Records
- D - 1 Found 1/2" iron in gravel road bed, per survey recorded in Liber 4, Page 291 of the Sanilac County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C - 1 NW Cor Section 5 T10N-R16E Found 1/2" iron
- D - 1 N 1/4 Cor Section 5 T10N-R16E Found 1/2" iron

SURVEY &
REMONUMENTATION
1993
COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C - 1 NW Cor Section 5 T10N-R16E Found 1/2" iron
S30°E 100.40' to a nail in a Power Pole
N20°E 140.70' to a nail in a Power Pole
S10°W 19.07' to the South end of a CMP
N10°W 19.00' to the North end of a CMP
- D - 1 N 1/4 Cor Section 5 T10N-R16E Found 1/2" iron
South 29.70' to a nail in a 18" Cedar
S15°W 86.30' to the NE Cor of a House
S45°E 46.25' to a nail in a 24" Maple
N30°E 40.10' to a nail in a 6" Ash

Signed by John A. Milletics Date Dec. 15, 1993
Surveyor's Michigan License No. 25859