

REMONUMENTATION CORNER

LIBER 1 PAGE 399

93 DEC 15 PM 3:18

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970 LIBER NO. 1 PAGE NO. 399

For corners in

ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

<u>Sanilac</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>16E</u>	E - 1, <u>F - 1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John A Milletics, in a field survey on Nov 5, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- E - 1 Found 1/2" iron in gravel road bed, per survey recorded in Liber 4, Page 58 of the Sanilac County Records
 - F - 1 Found 1/2" iron in gravel road bed, per survey recorded in Liber 4, Page 64 of the Sanilac County Records

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- | | |
|--|---|
| E - 1
NW Cor Section 4 T10N-R16E
Found 1/2" iron bar | F - 1
N 1/4 Cor Section 4 T10N-R16E
Found 1/2" iron bar |
|--|---|

SURVEY &
REMONUMENTATION
1993
COMMISSION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- | | |
|---|--|
| E - 1
NW Cor Section 4 T10N-R16E
Found 1/2" iron bar
North 19.09' to the West leg of a Road Sign
S45°W 84.20' to a nail in a Power Pole
S55°W 49.00' to a nail in a 18" Maple
S30°E 41.65' to a Stop Sign | F - 1
N 1/4 Cor Section 4 T10N-R16E
Found 1/2" iron bar
North 15.50' to the West leg of a Road Sign
S50°E 61.10' to a nail in a Power Pole
S40°E 55.35' to a nail in a Fence Post |
|---|--|

Signed by John A Milletics Date Dec. 15, 1993
Surveyor's Michigan License No. 25859