

MONUMENTATION

FEB 22 1996

LIBER

2 PAGE 71

RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

95 DEC -6 PH 2:49

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 71

For corners in

Sanilac

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 10N R 16E
- 2. Property Controlling S T R
- 3. Miscellaneous S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

F - 5 G - 5

ESTHER LEE REGISTER OF DEEDS SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

John A Millettics in a field survey on Oct 13, 19 95 to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

- F - 5 GLO Notes Set Post at 40.15 Chains Hemlock 30 N20W 10 Beech 12 S43E 28 1/2 Act 74 Form None Act 132 Form None Unrecorded Survey Dated Oct 1990
- G - 5 GLO Notes Set Post at 80.00 Chains Pine 18 S65W 1 Pine 22 N65E 1 Act 74 Form None Act 132 Form None Unrecorded Surveys Dated Oct 1990, Aug 1992, June 1993

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F - 5 S 1/4 Cor Section 9 T10N-R16E Found P.K. Nail in Black top equal distance between SE and SW Cor 2648.8'

G - 5 SE Cor Section 9 T10N-R16E Found 1" in Blacktop Road Surface

Approved Peer Board Meeting

Dec 6, 1995 [Signature]

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F - 5 S 1/4 Cor Section 9 T10N-R16E Monu Box South 55.15 to a nail in a Fence Post South 60.10 to a nail in a 24" Poplar North 49.65 to a nail in a Fence Post N60°W 113.7 to a nail in a Power Pole

G - 5 SE Cor Section 9 T10N-R16E Monu Box N40°E 62.0 to a nail in a Power Pole S45°W 62.3 to a nail in a Anchor Pole S45°E 41.50 to s Stop Sign West 2648.80 to the S 1/4 Cor

signed by [Signature]

Date NOV 23, 1995

Surveyor's Michigan License No. 25859

