

RECEIVED FOR RECORD

94 AUG 12 PM 2:36

LIBER NO. 1 PAGE NO. 453
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

REMONUMENTATION

LIBER 1 PAGE 453

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Sanilac</u> (County)	Located In:	Corner Code #/
1. Public Land Survey	T <u>10N</u> R <u>16E</u>	<u>G - 13, F - 13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on July 19, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G - 13 Found 1" Bar in gravel road bed as per survey dated Aug 1973 by William Soderberg

F - 13 Found 1/2" Iron Bar in gravel road bed as per survey dated Aug 1973 by William Soderberg.

Approved Peer Board Meeting
Aug. 9, 1994 *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G - 13
SE Cor section 33 T10N-R16E
Found 1" Pipe

F - 13
S 1/4 Cor Section 33 T10N-R16E
Found 1/2" Iron Bar

SURVEY &
REMONUMENTATION

SEP 07 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G - 13
SE cor Section 33 T10N-R16E
1" Pipe
West 58.40 to the centerline of Pavement
N05°E 50.30 to a nail E side of a Power Pole
N45°E 66.35 to a nail SE side of a Power Pole
S70°W 99.70 to a nail S side of a Anchor Pole

F - 13
S 1/4 Cor Section 33 T10N-R16E
1/2" Iron Bar
North 39.50 to a nail W side of a 18" Elm
N45°W 42.80 to a nail SW side of a 36" Elm
S60°W 81.80 to a nail N side of a 24" Ash
West 98.28 to a 1/2" iron bar being the
N 1/4 Cor Section 4

Signed by *John A Milletics*
Surveyor's Michigan License No. 25859

Date *July 24 1994*