

REMONUMENTATION

LIBER 1 PAGE 452

RECEIVED FOR RECORD

94 AUG 12 PM 2:36

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 1 PAGE NO. 452
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac
(County)

Located In:

Corner Code #

1. Public Land Survey

T 10N R 16E

I - 13, H - 13

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on July 18, 19 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I - 13 Found 5/8" Iron Bar in gravel road bed, as per Survey dated Jan 2, 1979 Sanilac Land Surveying

H - 13 Found 5/8" Iron Bar in gravel road bed as per Collins Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I - 13
SE Cor Section 34 T10N-R16E
Found 5/8" Iron Bar

H - 13
S 1/4 Cor Section 34 T10N-R16E
Found 5/8" Iron Bar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I - 13
SE Cor Section 34 T10N-R16E
5/8" Iron Bar
N05°W 96.10 to a nail E side of a Power Pole
N40°E 119.0 to a nail E side of a Power Pole
East 25'± to the centerline of a gravel road to the north.
S60°W 57.60 to a nail NW side of a 18" Poplar

H - 13
S 1/4 Cor Section 34 T10N-R16E
5/8" Iron Bar
S05°W 31.30 to nail E side of a 24" Maple
S30°E 40.40 to a nail W. side of a 24" Maple
S30°W 38.10 to a nail W. side of a 12" Pine
North 54.80 to a nail W. side of a Power Pole

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Approved Peer Board Meeting
Aug. 9, 1994

R-LK
gm

SURVEY &
REMONUMENTATION

SEP 07 1994

COMMISSION

Signed by John A Milletics

Date July 24, 1994

Surveyor's Michigan License No. 25859