

RECEIVED FOR RECORD

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

93 DEC 28 AM 10:39

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 1 PAGE NO. 419
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO. MICHIGAN

For corners in

SANILAC
(County)

Located In:

Corner Code #

- 1. Public Land Survey T10N R 16E
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

H - 1, I - 1

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Milletics, in a field survey on Dec 23, 19 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H - 1

Found 1/2" iron bar in gravel road bed, per iron found in survey dated 1-20-1988.

I - 1

Found 1" iron bar in gravel road bed, per iron bar found on survey dated 9-4-1978 Sanilac Land Surveying.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H - 1

N 1/4 Cor Section 3 T10N-R16E
Found 1/2" iron bar

I - 1

NE Cor Section 3 T10N-R16E
Found 1" iron bar

SURVEY &
REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H - 1

N 1/4 Cor Section 3 T10N-R16E
1/2" iron bar
South 75.12' to a nail in a thorn apple tree
S20°E 24.40' to the East end of a 12" CMP
S30°W 29.20' to the West end of a 12" CMP
East 2608.22' to the NE Cor of Section 3

I - 1

NE Cor Section 3 T10N-R16E
1" Iron Bar
N10°E 15.40' to the East leg of a road sign
N50°W 38.75' to a nail in a Tele Pole
S45°E 51.65' to a nail in a cable route sign
West 2608.22' to the N 1/4 Cor Section 3

Signed by John A Milletics

Date Dec 24, 1993

Surveyor's Michigan License No. 25859