

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED FOR RECORD

93 DEC 28 AM 10:39

LIBER 1 PAGE NO. 420
F. STINICK LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac
(County)

Located In:

Corner Code #

Table with 3 columns: Item description, Located In (T, R, S), and Corner Code #. Includes items like Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

1. John A Milletics, in a field survey on Dec. 23, 1993
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J - 1
Found 1/2" iron bar in gravel road bed, per iron bar found survey dated 9-4-1978 Sanilac Land Surveying.
K - 1
Found 5/8" iron bar in gravel road bed, per survey dated 7-23-1974, recorded Liber 2 Page 561 of the Sanilac County records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J - 1
N 1/4 Cor Section 2 T10N-R16E
Found 1/2" iron bar
K - 1
NE Cor Section 2 T10N-R16E
Found 5/8" iron bar

SURVEY &
REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

J - 1
N 1/4 Cor Section 2, T10N-R16E
1/2" iron bar
South 6'± to the centerline of Townsend Rd.
N60°E 87.90' to a nail in a 6" Poplar
South 42.85' to a nail in a Tele Pole
S45°W 45.89' to a nail in a 12"Cedar
K - 1
NE Cor Section 2, T10N-R16E
5/8" iron bar
N45°E 29.80' to a nail in a 12" Ash
N60°W 45.00' to a 12"CMP
S20°E 44.80' to a Stop Sign

Signed by John A Milletics

Date Dec. 24, 1993

Surveyor's Michigan License No. 25859