

REMONUMENTATION SURVEY & REMONUMENTATION  
 APR 10 1995  
 COMMISSION

RECEIVED FOR RECORD

94 DEC 16 AM 9:41

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 29  
 ESTHER LEE  
 REGISTER OF DEEDS  
 SANILAC CO., MICHIGAN

For corners of Sanilac (County) Located In: Corner Code #

1. Public Land Survey	T 10 N R 16 E	L - 13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on Oct 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 L - 13 GLO Notes  
 Set Post Beech 22 N 5 1/2 W 16, Beech 9 N 81 W 34

Approved Peer Board Meeting  
 Dec. 16, 1994 *[Signature]*

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Act 74 Forms None  
 Act 132 Forms None

Unrecorded Surveys Sanilac Land Survey dated 1982  
 Collins Survey dated 1974

Road Comm NONE  
 Drain Comm NONE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 L - 13  
 S 1/4 Cor Section 36 T10N-R16E  
 Found 3/4" Iron Pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L - 13  
 S 1/4 Cor Section 36 T10N-R16E  
 Found 3/4" Pipe, Set 1/2" iron with cap 25859  
 West 27.97 to a 1/2" iron (N 1/4 Cor Section 1)  
 South 47.13' to a nail West side of a Power Pole  
 S80°W 215.70' to a nail West side of a Power Pole  
 North 33.00 to a 1" Pipe



Signed by *[Signature]* Date Dec 5, 1994

Surveyor's Michigan License No. 25859