

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

93 DEC 28 AM 10:39

For corners in

LIBER NO. / PAGE NO. 421
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Sanilac (County)	Located In:	Corner Code #
1. Public Land Survey	T 10N R 16E	L - 1, M - 1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat: _____
5. Private Claims _____

I, John A Milletics, in a field survey on Dec. 23, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L - 1

Found 1/2" iron bar in gravel road bed, per iron bar found in survey dated 4-24-1989 Milletics Land Surveying.

M - 1

Found Monu Box in US 25, per State Highway records and as recorded in the Bryant-Duffield Lake Huron Subdivison, Liber 3, Page 18 of the Sanilac Co. Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L - 1

N 1/4 Cor Section 1 T10N-R16E
Found 1/2" iron bar

M - 1

NE Cor Section 1 T10N-R16E
Found Monu Box

SURVEY &
REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L - 1

N 1/4 Cor Section 1 T10N-R16E
1/2" iron Bar
N45°E 45.48' to a nail in a 8" Cherry Tree
South 65.22' to a nail in a clump of Poplars
S60°E 99.10' to a nail in a 24" Maple
N45°W 54.15' to a nail in a 8" Pine
East 2649.00' to the NE Cor Section 1

M - 1

NE Cor Section 1
Monu Box
N45°E 48.10' to a nail in a Guard Rail Post
N45°W 54.81' to a nail in a Guard Rail Post
S60°E 32.27' to the North Leg of a Road Sign
West 2.45' to the Centerline U.S. 25
West 2649.00' to the N 1/4 Cor Section 1

Signed by

John A Milletics

Date

Dec. 24, 1993

Surveyor's Michigan License No.

25859