

94 AUG 12 PM 2:37

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 1 PAGE NO. 456
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

For corners in

Sanilac

(County)

Located In:

Corner Code #

1. Public Land Survey	T	10N	R	16E	M - 2, M - 3
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John A Milletics, in a field survey on July 16, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
M - 2 Found Monu Box in place as per Survey recorded in Liber 3 on Page 3 of the Sanilac County Records.

M - 3 Found Monu Box in place in pavement as shown on the Michigan State Highway Right Way Book on Page 36

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Approved Peer Board Meeting
Aug. 9, 1994 *[Signature]*
gm

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 2
E 1/4 Cor Section 1 T10N-R16E
Found Monu Box

M - 3
SE Cor Section 1 T10N-R16E
Found Moun Box

SURVEY &
REMONUMENTATION

SEP 07 1994

COMMISSIONER

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 2
E 1/4 Cor Section 1 T10N-R16E
Monu Box
East 48.20 to a nail N side of a Power Pole
N60°W 81.3 to the SE Cor of a Michigan Bell Box
N40°E 92.85 to a nail NW side of a Power Pole
East 31.60 to the N Leg of a Road Sign

M - 3
SE Cor Section 1 T10N-R16E
Monu Box
S45°W 54.30 to a nail SE side of a Tele Pole
N45°W 59.00 to a nail NE side of a Anchor Pole
N45°E 58.85 to a nail SE side of a Tele Pole
S45°E 72.00 to a nail NE side of a Anchor Pole

Signed by *[Signature]*
Surveyor's Michigan License No. 25859

Date July 23, 1994