

REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 AUG 12 PM 2:37

For corners in

LIBER NO. 1 PAGE NO. 457
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Sanilac
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 10N R 16E M - 4 M - 5
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A. Millettics, in a field survey on July 16, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M - 4 Found Moun Box 5.8 West of existing centerline verified by numbers surveys and the Ballantrae Sub recorded in Liber 2 on Page 41

M - 5 Found Monu Box as shown on Page 36 of the State Highway Right of Way Book. Also verified by the Ballantrae Sub recorded in Liber 2 on Page 41 of the Sanilac County Records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M - 4
E 1/4 Cor Section 12 T10N-R16E
Found Monu Box

Approved Peer Board Meeting
Aug. 9, 1994 *RLX*

M - 5
SE Corner Section 12 T10N-R16E
Found Monu Box

SURVEY &
REMONUMENTATION

SEP 07 1994

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M - 4
E 1/4 Cor Section 12 T10N-R16E
Monu Box
East 5.80 to the existing centerline of U.S 25
S40°W 81.40 to a nail NW side of a 18" Pine
N70°W 87.40 to the SE cor of a house
N80°E 80.30 to a nail S side of a 18" Pine
S80°E 70.80 to a nail N side of a 18" Pine

M - 5
SE Cor Section 12 T10N-R16E
Monu Box
S45°W 62.70 to a nail NW side of a Tele Pole
S45°E 72.80 to a nail NE side of a Anchor Pole
N45°E 56.65 to a nail N side of a Power Pole
N60°W 50.15 to centerline of a Gas Cap in the curb

Signed by John A. Millettics
Surveyor's Michigan License No. 25859

Date July 23, 1994