

**SURVEY & REMONUMENTATION**

LIBER 2 PAGE 291

RECEIVED FOR RECORD

SEP 17 1999

1999 REMONUMENTATION PROGRAM  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

99 AUG -2 AM 9:08

LIBER NO. 2 PAGE NO. 291  
 MICHELE VANNORMAN  
 REGISTER OF DEEDS  
 SANILAC CO., MICHIGAN

For corners in SECTION

SANILAC

(County)

Located in:

Corner Code #

*Seg. #2 pm*

- |                                    |                             |       |
|------------------------------------|-----------------------------|-------|
| 1. Public Land Survey              | T <u>11</u> N R <u>12</u> E | A-1   |
|                                    | T ___ R ___                 | _____ |
|                                    | T ___ R ___                 | _____ |
|                                    | T ___ R ___                 | _____ |
| 2. Property Controlling in Section | S ___ T ___ R ___           | _____ |
|                                    | S ___ T ___ R ___           | _____ |
| 3. Miscellaneous Property in Sec.  | S ___ T ___ R ___           | _____ |
|                                    | S ___ T ___ R ___           | _____ |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, John A. Milletics, in a field survey on April 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S.-Set temporary Township corner at 80.00 chains; Township corner established at 79.21 chains-Hemlock 15 North 7; Hemlock 28 S29W 8 1/2; W. Ash 20 N6E 29; Hemlock 28 S29W 8 1/2; Birch 17 S29W 41; Hemlock 28 S29W 21 1/2
- 1882 (County Surveyor's Record) John A. Teskey, Tuscola County Surveyor-Established proportionate distance from identified corners and sight trees-Stake S45W 70 links; Stake N45W 70 links
- 1963 (Michigan State Highway Department witness card) Donald C. Pyle, P.S. 3165-Found 1" Pipe buried 2' deep-S22°E 62.42' 29" Elm; N20°E 90.15' 26" Tw Elm; North 90.39 27" Tw Elm
- 1987 (Survey-Liber 578, pages 58 and 59) Kenneth D. Dunton, P.S. 23503-Fnd 1" pipe in Mon. box North 1.0' center line of M-46; S20°W 56.3' S end of curb; S45°W 48.9' W end of curb

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 1  
 NW Corner Section 6 T11N-R12E  
 Found Monu Box with Brass cap affixed to 5/8" Iron Bar in Box.  
 North 2623.24' to W 1/4 Corner  
 South 2594.76 to W 1/4 Corner  
 Accepted as best evidence

APPROVED PEER BOARD MEETING  
 July 20, 1999 *JM*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 5/8" diameter by 12" long reinforcing rod with Standard 2" Brass cap affixed inside, found 1" Pipe inside Monument Box

- N50°E, 46.29' set 1/2" diameter reinforcing rod
- S40°E, 48.28' set 1/2" diameter reinforcing rod 1 ft. behind back of concrete curb
- S50°W, 45.70' set 1/2" diameter reinforcing rod 1 ft. behind back of concrete curb
- N40°W, 44.63' set 1/2" diameter reinforcing rod

Signed by *John A. Milletics*  
 Surveyor's Michigan License No. 25859

Date June 29, 1999

