

SURVEY & REMONUMENTATION

SEP 17 1999

LIBER 2 PAGE 294

RECEIVED FOR RECORD

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

99 AUG -2 AM 9:09

SECTION

For corners in

LIBER NO. 2 PAGE NO. 294
 MICHELE YANNORMAN
 REGISTER OF DEEDS
 SANILAC CO., MICHIGAN

<u>SANILAC</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11</u> N <u>12</u> E	<u>A-4</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, John A. Millettics, in a field survey on April 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S.-Set quarter Section post-Beech 10 N13W 38; Elm 12 S57W 28
 - 1886 (County Surveyor's Record) John A. Teskey, Tuscola County Surveyor-Perpetuated by: Stake; East 50 links to Stake; West 50 links to Stake
 - 1973 (Survey-Liber 431, page 387) Harold N. Elrich, P.S. 18986-Fnd. 5/8" iron-East 25.85' Cor. post; S35°E 50.30' 5" Elm
 - 1973 (Land Corner Recordation Certificate) Harold N. Elrich P.S. 18986 Fnd. 5/8" Iron-same accessories as on above Survey
 - 1977 (Land Corner Recordation Certificate) Kenneth D. Dunton, P.S. 23503-Fnd. 5/8" Iron-East 25.8 Cor. post nail & flagging; S35°E 50.30' 5" Elm nail and flagging; West 45.07' RLS 11192 tag in PP

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 4
 W 1/4 Corner Section 7 T11N-R12E
 Found Standard Concrete Monument with Brass Cap
 North 2659.29 feet to the NW Corner
 South 2640.21 feet to the SW Corner
 Accepted as best evidence

APPROVED PEER BOARD MEETING
 July 20, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found standard Concrete Monument W/2" Brass Cap
 N50°E, 22.47' "V" notch in South end @ top of 12" Corrugated steel culvert
 N85°E, 26.76' T.C. Remon. tag in South face of Telephone pole stub
 S35°W, 20.13' set 1/2" diameter reinforcing rod
 N80°W, 45.13' T.C. Remon. tag in North face of power pole



Signed by [Signature]
 Surveyor's Michigan License No. 25859

Date June 30, 1999