

**SURVEY & REMONUMENTATION**

SEP 17 1999

LIBER 2 PAGE 297

RECEIVED FOR RECORD

99 AUG -2 AM 9:09

SECTION

1999 REMONUMENTATION PROGRAM  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER NO. 2 PAGE NO. 297  
MICHELE VANNORMAN  
REGISTER OF DEEDS  
SANILAC CO., MICHIGAN

For corners in

SANILAC

(County)

Located In:

Corner Code #

- 1. Public Land Survey T11NR 12E A-7  
T R  
T R  
T R
- 2. Property Controlling in Section S T R  
S T R
- 3. Miscellaneous Property in Sec. S T R  
S T R

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, John A. Millettics, in a field survey on April 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

- A. Description of original monument and accessories and/or subsequent restoration:
- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S.-Set post Cor. Sections 13,24-Hemlock 22 N6W 12; Hemlock 10 S44 1/2 W 25
  - 1974 (Survey-Liber 438, page 726) Robert G. Kay, P.S. 14096-shows SE Cor., Sec. 13, T11N-R11E no mention of character of marker found of set, N40°W 80.52' Nail in P.P.; N55°E 48.71' Nail in P.P.; S05°E 27.64' Nail in T.P.
  - 1975 (survey-Liber 448, page 320) Robert G. Kay, P.S. 14096-Fnd. 1/2" Iron-accessories same as above Survey
  - 1980 (Survey-Liber 508, page 866) Charles Getz, P.S. 25843-same marker & accessories as above survey
  - 1986 (Survey-Liber 560, pages 1038 & 1040) Charles Getz, P.S. 25843-same Marker-N40°W 80.52' Nail in P.P.; S05°E, 27.64' Nail in T.P. N60°E 46.21' Face Road Sign
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 7  
SW Corner Section 18 T11N-R12E  
Found Standard Concrete Monument with Brass Cap  
South 2632.21 feet to the W 1/4 Corner  
North 2642.45 feet to the W 1/4 Corner  
Accepted as best evidence

APPROVED PEER BOARD MEETING  
July 20, 1999

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Found Standard Concrete Monument W/2" Brass Cap
  - N55°E, 46.17' SW face of 2" diameter steel post
  - S02°E, 27.41' T.C. Remon. tag over found nail and disc in West face of Telephone pole stub
  - S55°W, 21.22' Set 1/2" diameter reinforcing rod
  - N35°W, 80.53' T.C. Remon. tag over found nail and disc in SW face of power pole

Signed by John A. Millettics  
Surveyor's Michigan License No. 25859

Date June 30, 1999

