

SURVEY & REMONUMENTATION

SEP 17 1999

LIBER

2 PAGE 298

RECEIVED FOR RECORD

SECTION

1999 REMONUMENTATION PROGRAM
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

99 AUG -2 AM 9:09

LIBER NO. 2 PAGE NO. 298

MICHELE VANNORMAN
 REGISTER OF DEEDS
 SANILAC CO., MICHIGAN

For corners in

<u>SANILAC</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T11N R12E	A-8
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, John A. Milletica, in a field survey on April 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1834 (Gov't. Land Office Notes) Harvey Parke, D.S.-set quarter section post-Cedar 10 N43W 20; B. Ash 10 S76W 9
- 1986 (Survey-Liber 560, pages 1038 & 1040) Charles S. Getz P.S. 25843-drawing shows 1/2" Iron @ Old Cor Post, no indication whether found or set and gives no accessories

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A - 8
 W 1/4 Corner Section 19 T11N-R12E
 Found Standard Concrete Monument with Brass Cap
 South 2650.94 feet to SW Corner Section 19
 North 2632.21 feet to NW Corner Section 19
 Accepted as best evidence

APPROVED PEER BOARD MEETING
 July 20, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found Standard Tuscola County Concrete Monument W/2" Brass Cap stamped M8 T11N-R12E
 N02°E, 102.24'-T.C. Remon. tag in West face of 18" Elm
 S85°E, 32.07'-T.C. Remon. tag in South face of 14" Elm
 N85°W, 75.91'-T.C. Remon. tag in North face of 14" Apple Tree
 N05°W, 49.75'-T.C. Remon. tag in East face of 10" Elm



Signed by John A. Milletica
 Surveyor's Michigan License No. 25859

Date June 30, 1999