

LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

DEC 16 1996

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>11</u> N. <u>12</u> E. <u>12</u>		C - 13 <u>D - 13</u>
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. _____ E. _____ S., R. _____ W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. _____ E. _____ S., R. _____ W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

COMMISSION
RECEIVED FOR RECORD
93 NOV -8 PM 1:39
LIBER NO. 1 PAGE NO. 390
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN
REGISTER OF DEEDS STAMP AND FILING NUMBER

I, John A Milletics, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Aug 21, 1993, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

C - 13 Found P.K. nail in blacktop as recorded in Liber 3, Page 302 of the Sanilac County Records also corner is varied by numerous plats in the City of Marlette.

D - 13 Found R/R Spike in blacktop as recorded in Liber 4 page 415 of the Sanilac County Records, also varied by numerous plats in the City of Marlette.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

C - 13
SW Cor Section 32 T11N-R12E
Found P.K. nail

D - 13
S 1/4 Cor Section 32 T11N-R12E
Found R/R Spike

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C - 13
SW Cor Section 32 T11N-R12E
Monu Box Set
N30°E 74.25' to the SW Cor Church
N30°W 84.28' to Pillor on House
S30°E 85.55' to NE Cor of House

D - 13
S 1/4 Cor Section 32 T11N-R12E
Monu Box Set
North 31.70' to a acorn post
S10°W 36.05' to a nail in a 36" Maple
S45°E 61.55' to a nail in a 36" Maple

SIGNED BY [Signature] DATE Nov 4, 1993

SURVEYOR'S MICHIGAN REGISTRATION NO. 25859

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

