

REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 1 PAGE 394

For corners in

Sanilac (County) Located In: Corner Code #
 1. Public Land Survey T 11N R 12E J - 13, K - 13
 T ___ R ___
 T ___ R ___
 T ___ R ___
 2. Property Controlling S ___ T ___ R ___
 in Section S ___ T ___ R ___
 3. Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___
 4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

RECEIVED FOR RECORD

93 DEC 14 PM 3:00

LIBER NO. 1 PAGE NO. 394
 ESTHER LEE
 REGISTER OF DEEDS
 SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

I, John A Milletics, in a field survey on Aug 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 J - 13 Found Railroad Spike as recorded in Liber 4 Page 22 of the Sanilac County Records
 K - 13 Found Railroad Spike as recorded in Liber 4 Page 22 of the Sanilac County Records

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 J - 13
 S 1/4 Cor Section 35 T11N-R12E
 Found Railroad Spike
 K - 13
 SE Cor Section 35 T11N-R12E
 Found Railroad Spike

SURVEY &
 REMONUMENTATION
 1993
 COMMISSION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 J - 13
 S 1/4 Cor Section 35 T11N-R12E
 Set Monu Box
 North 54.75' to a nail in a Power Pole
 N10°E 47.65' to the East End of a 12" CMP
 East 2644.09' to the SE Cor Section 35
 K - 13
 SE Corner Section 35 T11N-R12E
 Set Monu Box
 N45°W 65.45' to a Nail in a Power Pole
 N45°E 74.60' to a Nail in a Power Pole
 South 20.28' to the West leg of a Arrow Sign
 West 2644.09' to the S. 1/4 Cor Section 35

Signed by John A Milletics Date Dec 13, 1993
 Surveyor's Michigan License No. 25859