

For corners in

Sanilac
(County)

Located In:

Corner Code -##

- | | | |
|------------------------------------|---------------------------|-----------------------|
| 1. Public Land Survey | T <u>11N</u> R <u>12E</u> | <u>L - 13, M - 13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD

93 DEC 14 PM 3:00

LIBER 1 PAGE NO. 395
ESTHER LEE
REGISTER OF DEEDS
SANILAC CO., MICHIGAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John A Milletics, in a field survey on Aug 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L - 13 Found Railroad Spike in Blacktop in centerline equal distance between SE cor Section 36 and SW Cor Section 36

M - 13 Found Railroad Spike in Blacktop used survey Recorded Nov 2, 1903 by Bert Walker to verify.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L - 13
S 1/4 Cor Section 36 T11N-R12E
Found Railroad Spike

M - 13
SE Cor Section 36 T11N-R12E
Found Railroad Spike

SURVEY &
REMONUMENTATION

1993

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L - 13
S 1/4 Cor Section 36 T11N-R12E
Set Monu Box
East 13.00' to the N 1/4 Cor Section 6 (Monu Box)
N45°W 131.20' to a nail in a Power Pole
S10°E 53.22' to a nail in a Double Poplar

M - 13
SE Cor Section 36 T11N-R12E
Set Monu Box
East 10.88' to the NW Cor Section 5
North 56.75' to a nail in a Power Pole
N45°W 71.20' to a nail in a Power Pole
S45°W 63.70' to a nail in a 24" Poplar

Signed by John A Milletics

Date Dec 15, 1993

Surveyor's Michigan License No. 25859